Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate in Rs.	Amount in Rs.
			N1	N2	L	B	D			
	Third Floor									
	Same as Internal Plastering qty vide							914.10		
	Terrce Floor							52.50		
								5590.40		
							Say	**5590.40**	**97.20**	**543386.88**
29	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on **ceiling** and / or **sloping roof** as per specifications.									
	(P.No.117, I.No.15.51.2 of PW,P & IWTD S.R 2016-17)									
	Ground Floor									
	Same as Internal Ceiling Plastering qty vide							996.30		
	First Floor									
	Same as Internal Ceiling Plastering qty vide							995.60		
	Second Floor									
	Same as Internal Ceiling Plastering qty vide							1229.90		
	Third Floor									
	Same as Internal Ceiling Plastering qty vide							1229.90		
	Terrce Floor							52.50		
								4504.20		
							Say	**4504.20**	**101.52**	**457266.38**
29	Providing & finishing **external walls** in two coats over one coat of **100 % acrylic silcon glazed** primer with **Antifungal paint** for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications									
	(P.No.125, I.No.15.104 of PW,P & IWTD S.R 2016-17)									
	Ground Floor							354.40		
							Say	**354.40**	**166.32**	**58943.81**
	First Floor			1				427.00		
							Say	**427.00**	**169.56**	**72402.12**
	Second Floor			1				586.60		
							Say	**586.60**	**172.80**	**101364.48**
	Third Floor			1				586.60		
							Say	**586.60**	**176.04**	**103265.06**
	Terrce Floor			1				354.30		
							Say	**354.30**	**179.28**	**63518.90**
30	KSRB 15-17.5 : Applying priming coat over **new wood surface** and / or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications.									
	(P.No.119, I.No.15.59 of PW,P & IWTD S.R 2016-17)	**Sqm**								
	D1		2	12	1.00	--	2.100	**50.40**	**44.28**	**2231.71**
31	Providing and applying painting two coats on **new wood surface and/ or wood based surface with enamel paint** to give an even shade, cleaning the surface of all dirt, dust and foregn matter, sand papering including cost of materials, labour complete as per specifications.									
	(P.No.119, I.No. 15.60.1of PW,P & IWTD S.R 2016-17)									
	All floors									
	Qty Same as Vide item no			1			Say	**50.40**	**90.72**	**4572.29**
32	KSRB 15-18.1 : Applying **Red lead ready** mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.									
	(P.No.121, I.No.15.73 of PW,P & IWTD S.R 2016-17									
	From all Floors									
	Window Grills,			1	232.80			232.80		
	Collapsible shutters			1	55.30			55.30		
	Rolling Shutter			1	727.80			727.80		
								1015.90		
							Say	**1015.90**	**31.32**	**31817.99**

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate in Rs.	Amount in Rs.
			N1	N2	L	B	D			
33	KSRB 15-18.2 : Providing and applying **enamel metal paint** two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.									
	(P.No.121, I.No.15.74of PW,P & IWTD S.R 2016-17)									
	Same as vide quantity			1	1015.90			1015.90		
							Say	**1015.90**	**88.56**	**89968.10**
		TOTAL AMOUNT OF PLASTERING & FINISHES								**5433400.62**
	FLOORING WORK									
34	KSRB 14.10-2: Flooring with 20 mm thick polished **shahabad slabs** using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Specification No. KBS									
	(P.No.103, & I.No.14.16 of KPWD S.R 2016-17)									
	Ground Floor									
	Shop (3X6.8)			16	3.00	6.80	--	326.40		
	Skirtng			1	19.60	0.15	--	2.94		
	Shop (3X3.3)			18	3.00	3.30	--	178.20		
	Skirting			1	12.60	0.15	--	1.89		
								509.43		
							Say	**509.50**	**1294.92**	**659761.74**
	First Floor									
	Shop (3X3.1)			50	3.00	3.10	--	465.00		
	Skirting			50	9.10	--	0.150	68.25		
								533.25		
							Say	**533.30**	**1296.54**	**691444.78**
35	KSRB 14.7-2 : Providing and laying red oxide flooring 40 mm thick, with an under layer of 30mm thick M-15 cement concrete, using broken granite metal of 12.5mm nominal size and top layer of 10mm thick plaster with 1:3 cement mortar mixed with red oxide (using 3.5 kg of red oxide per 50 kg of cement) finished with floating coat of neat cement mixed with red oxide (mix of same proportion), including cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.3									
	Ground Floor									
	Stair Case Waist Slab			1	57.60	4.70	--	270.72		
								270.72		
							Say	**270.80**	**624.24**	**169044.19**
	First Floor									
	Corridor			1	58.00	4.70	--	272.60		
							Say	**272.60**	**625.86**	**170609.44**
36	Providing and fixing for flooring 40mm thick **sadarhalli grey** flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3.									
	(P.No.109, & I.No.14.57 of KPWD S.R 2016-17)									
	Second Floor									
	Office Toilet			2	6.00	3.00	--	36.00		
	Deduct Wc			4	1.45	1.20	--	6.96		
	General Toilet			1	6.20	4.30	--	26.66		
	Deduct Wc			4	1.45	1.50	--	8.70		
								47.00		
							Say	**47.00**	**2045.52**	**96139.44**
	Third Floor									
	Same AsFirst Floor Qty						Say	**47.00**	**2047.14**	**96215.58**
37	Providing and laying **Hassan Green granite flooring** for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification.									
	(P.No.108, & I.No.14.51 of KPWD S.R 2016-17)									
	Ground Floor									
	Tread			20	1.50	0.30	--	9.00		
	Riser			19	1.50	--	0.150	4.28		
	Landing			2	1.60	1.50	--	4.80		
	Skirting			1	25.00	0.15		3.75		

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate	Amount
			N1	N2	L	B	D		in Rs.	in Rs.
								21.83		
							Say	**21.90**	**4305.96**	**94300.52**
	First Floor									
	Tread			21	1.50	0.30	--	9.45		
	Riser			22	1.50	--	0.150	4.95		
	Landing			2	1.60	1.50	--	4.80		
	Skirting			1	25.00	0.15		3.75		
								22.95		
	Same As First Floor Qty						Say	**23.00**	**4307.58**	**99074.34**
	Second Floor									
	Same As First Floor Qty						Say	**23.00**	**4309.20**	**99111.60**
	Third Floor									
	Same As First Floor Qty						Say	**23.00**	**4310.82**	**99148.86**
38	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick **water cut/gang saw Grey Granite,** Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm									
	(P.No.108, & I.No.14.48.1 of KPWD S.R 2016-17)									
	Ground Floor									
	Stair Case Loobby			1	5.50	6.20	--	34.10		
				1	2.50	1.00	--	2.50		
							Say	**36.60**	**2760.48**	**101033.57**
	First Floor									
	Stair Case Loobby			1	5.50	6.20	--	34.10		
				1	2.50	1.00	--	2.50		
							Say	**36.60**	**2762.10**	**101092.86**
	Second Floor									
	Stair Case Lobby			1	5.50	6.20	--	34.10		
				1	2.50	1.00	--	2.50		
	Entrance Lobby			1	6.60	4.30	--	28.38		
								64.98		
							Say	**65.00**	**2763.72**	**179641.80**
	Third Floor									
	Same As First Floor Qty						Say	**65.00**	**2765.34**	**179747.10**
39	Providing and fixing **Vitrified glazed tiles** of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification.									
	(P.No.107, & I.No.14.45 of KPWD S.R 2016-17)									
	Second Floor									
	Left Office Area			1	370.00	--	--	370.00		
	Right Office Area			1	290.00	--	--	290.00		
	Skirting									
	Left Office Area			1	85.00	--	0.150	12.75		
	Right Office Area			1	75.00	--	0.150	11.25		
	Staircase lobby wall cladding up to 1.5 mt			1	35.00	--	1.500	52.50		
								736.50		
							Say	736.50	1212.84	**893256.66**
	Third Floor									
	Same As First Floor Qty						Say	**736.50**	**1214.46**	**894449.79**
40	Providing **ceramic tiles** of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. **size 30x30cms**									
	(P.No.106, & I.No.14.36.2 of KPWD S.R 2016-17)									
	Second Floor									
	Office Toilet									
	Wc			8	1.45	1.20	--	13.92		
	General Toilet									

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate in Rs.	Amount in Rs.
			N1	N2	L	B	D			
	Wc			4	1.50	1.50	--	9.00		
								22.92		
	Third Floor						Say	**23.00**	**1273.32**	**29286.36**
	Same As First Floor Qty									
							Say	**23.00**	**1274.94**	**29323.62**
41	KSRB 14-17.2: Providing skirting, dado, rises of steps with **colour glazed tiles** on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.									
	Colour glazed tiles 30×60cms 6mm thick with border of size 30×10cms.									
	(P.No.106 I.No.14.41.2 of PW,P & IWTD S.R 2016-17)									
	Second Floor									
	Office Toilet			4	19.20	--	2.100	161.28		
	General Toilet			2	35.20	--	2.100	147.84		
								309.12		
	Deduction									
	toilet doors									
	D1			6	0.90	--	2.100	11.34		
	D2			12	0.75	--	2.100	18.90		
	Openings									
	O1			2	1.00	--	2.100	4.20		
	O2			2	0.90	--	2.100	3.78		
	O3			4	0.75	--	2.100	6.30		
	V			10	1.05	0.60	--	6.30		
								50.82		
						Total		258.30		
	Third Floor						Say	**258.30**	**1605.96**	**414819.47**
	Same As First Floor Qty									
							Say	**258.30**	**1607.58**	**415237.91**
		TOTAL AMOUNT OF FLOORING WORK								**5512739.63**
	WATER PROOFING WORK									
42	Providing and laying **Cinder concrete** in cement 1:15 (1 cement: **15 cinder of 12.5mm** nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.									
	(P.No. 46, I.No.8.4 of PW,P & IWTD S.R 2016-17)	**Cum**								
	Second Floor									
	Office Toilet			2	6.00	3.20	0.300	11.52		
	General Toilet			1	6.20	4.30	0.300	8.00		
								19.52		
							Say	**19.60**	**2054.16**	**40261.54**
	Third Floor									
	Same As First Floor Qty									
							Say	**19.60**	**2054.16**	**40261.54**
43	Providing **INTEGRAL CRYSTALINE** Waterproofing treatment to the sunken portion of toilets. Using Crystalline Slurry of approved make @ 1.40 kg per SQM in two coats (0.7 Kg per coat) confirming to ASTM S 1202 & DINV 18998 standards.									
	(P.No.280 I.No.38.11 of KPWD S.R 2016-17)									
	Second Floor									
	Third Floor			1	60.50	--	--	**60.50**	**518.40**	**31363.20**
				1	60.50	--	--	**60.50**	**518.40**	**31363.20**
		TOTAL AMOUNT OF WATER PROOFING WORK								**143249.47**
	JOINERY WORK									
44	Providing **White Sal Wood frames of doors,** windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications									
	(PWD SR 2016-17 Page No. 51 It. No 9.13)									
	Second & Third Floor									
	D1			6	6.30	0.125	0.075	0.35		
	D2			6	6.30	0.125	0.075	0.35		
								0.71		
							Say	**0.80**	**69034.68**	**55227.74**

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate	Amount
			N1	N2	L	B	D		in Rs.	in Rs.
45	Providing and fixing **flush door shutter** made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification.									
	(PWD SR 2016-17 Page No. 62 It.No 9.106.5)									
	Second Floor									
	D1			6	0.90	--	2.100	11.34		
								11.34		
							Say	**11.40**	3313.44	**37773.22**
	Third Floor									
	D1			6	0.90	--	2.100	11.34		
								11.34		
							Say	**11.40**	3313.44	**37773.22**
46	Providing and fixing 65mmx90mm **GRP Doorframe** fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame.									
	(PWD SR 2016-17 Page No. 60 It.No 9.95)	**MTR**								
	30mm thick one side teak and one side commercial									
	Second Floor									
	D2			12	6.3	--	--	75.60		
								75.60		
							Say	**75.60**	**524.88**	**39680.93**
	Third Floor									
	D2			12	6.3	--	--	75.60		
								75.60		
							Say	**75.60**	**528.12**	**39925.87**
47	Providing and fixing factory made single leaft rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and on layer of 45 gsm E-Glass Chopped strand Mat (CSM), impregnated with orthopthalic polyster resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not less than 28mmx32mm and also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc, shall be provided. A structural									
	(PWD SR 2016-17 Page No. 59 It.No 9.93)	**Sqm**								
	Second Floor									
	D2			12.00	0.75	--	2.100	18.90		
								18.90		
							Say	**18.90**	**3462.48**	**65440.87**
	Third Floor									
	D2			12.00	0.75	--	2.100	18.90		
								18.90		
							Say	**18.90**	**3465.72**	**65502.11**
48	KSRB 7.8 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28kg/m all duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows, not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and grinded electrically subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures,labour charges and HOM of machinery complete as per specifications.									
	(PWD SR 2016-17 Page No. 32 It.No 7.8)	**Sqm**								
	Ground Floor									
	Ventilators			36.00	1.80	--	0.60	38.88		
							Say	**38.90**	**3213.00**	**124985.70**

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate	Amount
			N1	N2	L	B	D		in Rs.	in Rs.
	First Floor									
	Ventilators			36.00	1.80	--	0.60	38.88		
							Say	**38.90**	**3218.40**	**125195.76**
49	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters									
	(PWD SR 2016-17 Page No. 43 It.No 7.11.2)	**Sqm**								
	Second Floor									
	W1			33	2.00	--	1.500	99.00		
	W2			2	1.50	--	1.500	4.50		
	Ventilators			14	0.90	--	0.750	9.45		
								112.95		
							Say	**113.00**	**4526.28**	**511469.64**
	Third Floor									
	W1			33	2	--	1.500	99.00		
	W2			2	1.5	--	1.500	4.50		
	Ventilators			14	0.9	--	0.750	9.45		
								112.95		
							Say	**113.00**	**4531.68**	**512079.84**
	Terrece Floor									
	Windows									
	W1			3	1.50	--	1.500	6.75		
								6.75		
							Say	**6.80**	**4537.08**	**30852.14**
49	Providing and fixing **M.S.grill work for windows and ventilators** weighing 21 kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifictions. Specification No. KBS 7.12 (**Considered 18 Kg/sqm)**									
	(P.No.32, I.No.7.9 of PW,P & IWTD S.R 2016-17)									
	Same as window and Ventilators qty			1	232.80	--	18.000	4190.40		
								4190.40		
							Say	**4190.40**	**84.24**	**352999.30**
50	KSRB 7.5 : Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel lathsof convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 mSpecification No. KBS 7.10 / 7.12									
	(P.No.31, I.No.7.5 of PW,P & IWTD S.R 2016-17)									
	Ground Floor									
	Rolling Shutter									
	RS1			13.00	3.00	--	2.55	99.45		
	RS2			22.00	2.90	--	2.55	162.69		
								262.14		
							Say	**262.20**	**3090.96**	**810449.71**
	First Floor									
	RS1			28.00	3.00	--	3.15	264.60		
	RS2			22.00	2.90	--	3.15	200.97		
								465.57		
							Say	**465.60**	**3096.36**	**1441665.22**
51	KSRB 7.1 : Providing and fixing in position **collapsible steel shutters** with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 7.7 / 7.12									
	(P.No.31, I.No.7.1 of PW,P & IWTD S.R 2016-17)									

Sl No	Description of work	Unit	No		Dimensions			Quantity	Rate in Rs.	Amount in Rs.
			N1	N2	L	B	D			
	Ground Floor									
	S1			2	3.50	--	3.150	22.05		
								22.05		
							Say	**22.10**	**4355.64**	**96259.64**
	First Floor									
	S1			1	3.50	--	3.150	11.03		
								11.03		
							Say	**11.10**	**4361.04**	**48407.54**
	Second Floor									
	S2			2	3.50	--	3.150	22.05		
								22.05		
							Say	**22.10**	**4366.44**	**96498.32**
	Third Floor									
	S2			2	3.5	--	3.150	22.05		
								22.05		
							Say	**22.10**	**4371.84**	**96617.66**
	Terrece Floor									
	S1			1	3.50	--	3.150	11.03		
								11.03		
							Say	**11.10**	**4377.24**	**48587.36**
52	Providing and fixing Stainless steel 304 Grade for staircase railing, Balconys Ramps with hand rails 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges etc., complete as per specification									
	(P.No.43 I.No.7.38 of PW,P & IWTD S.R 2016-17)	Sqm		1.00	30.00	--	1.20	36.00	**6644.16**	**239189.76**
53	KSRB 9-27.1 : Fixing of **door frame in an existing opening** including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.									
	(P.No.57, I.No.9.80 of PW,P & IWTD S.R 2016-17)									
	Second Floor									
	Door			6	--	--		**6.00**	1141.56	**6849.36**
	Third Floor									
	Door			6	--	--		**6.00**	1143.18	**6859.08**
		TOTAL AMOUNT OF JOINERY WORK								**4890290.00**
	ABSTRACT									
1	TOTAL AMOUNT FOR DEMOLITION WORK									**17456.00**
2	TOTAL AMOUNT FOR EARTH WORK									**1117239.64**
3	TOTAL AMOUNT FOR PCC & RCC WORK									**10323298.26**
4	TOTAL AMOUNT FOR SHUTTERING WORK									**3152114.12**
5	TOTAL AMOUNT FOR REINFORCEMENT WORK									**9720494.21**
6	TOTAL AMOUNT FOR MASONARY WORK									**2557223.35**
7	TOTAL AMOUNT OF PLASTERING & FINISHES									**5433400.62**
8	TOTAL AMOUNT OF FLOORING WORK									**5512739.63**
9	TOTAL AMOUNT OF WATER PROOFING WORK									**143249.47**
10	TOTAL AMOUNT OF JOINERY WORK									**4890290.00**
	TOTAL AMOUNT									**42867505.31**
	TOTAL COST J P MARKET BUILDING									**42867505.31**
	Misc to round off									**0.69**
										42867506.00
	Rupees Four Crore Twentyeight lakh Sixtyseven thousand five hundred six only									